BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/04/2019-20 Date: 12.06.2019

Indet No: BBMP/2018-19/RD/WORK_INDENT34928/CALL-2

SCHEDULE -B

Name of Work: Improvements of Road and Footpath in Jalahalli ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	430.56	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	117.00	Rupees One Hundred Seventeen Only
2	188.34	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	245.00	Rupees Two Hundred Forty Five Only
3	239.20	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 with solid concrete blocks of size 400x200x200mm	Sqm	1070.00	Rupees One Thousand Seventy Only
4	287.04	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cms thick	Sqm	1014.00	Rupees One Thousand Fourteen Only
5	287.04	Providing one line dressing to granite stone slab / granite stone masonry as per specifications	Sqm	997.00	Rupees Nine Hundred Ninety Seven Only
6	77.74	Providing and laying in position plain cement concrete of Mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fne aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifcations.	Cum	5924.00	Rupees Five Thousand Nine Hundred Twenty Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner